

JULY 1, 2025

# PRELIMINARIES

## LISKEARD GUILDHALL J24.004

Le Page **Architects** Ltd.  
Written By: SCr  
Plumer House, Tailyour Road, Crownhill, Plymouth, PL6 5DH

<b>A</b>	<b>PRELIMINARIES/GENERAL CONDITIONS</b>
<i>A10</i>	<i>PROJECT PARTICULARS</i>
A10.110	THE PROJECT: Name: Guildhall Liskeard Rainwater goods external decoration Nature: Refurbishment of existing components Location: Liskeard Guildhall, Fore Street, Liskeard Cornwall PL14 3JA Timescale for completion of the construction work: Summer 2025 (TBC)
A10.120	EMPLOYER (CLIENT): Liskeard Town Council, 3-5 West Street, Liskeard PL14 6BW
A10.127	THE PRINCIPAL CONTRACTOR: The Contractor
A10.140	ARCHITECT & PRINCIPAL DESIGNER (hereinafter referred to as 'CA'): Le Page Architects Ltd Plumer House Tailyour Road Crownhill Plymouth PL6 5DH
A11	TENDER AND CONTRACT DOCUMENTS
A11.110	THE TENDER DOCUMENTS are:  Schedule of works Drawing Nos J24.004 AS12, AS15
A11.120	THE CONTRACT DOCUMENTS will be the same as the tender drawings.
A11.160	THE PRE-TENDER CDM INFORMATION: Full RAMS, method statements and risk assessments are to be provided by the contractor prior to works commencement. To be adapted to the satisfaction of the CA as required.
<i>A12</i>	<i>THE SITE/EXISTING BUILDINGS</i>
A12.110	THE SITE is Liskeard Guildhall
A12.140	EXISTING MAINS/SERVICES: Water and electrical supplies are available on site.
A12.200	ACCESS TO THE SITE: Description, Via rear passageway to the north and via ladder access through flat roof access hatch to first floor of building and generally from West Street Liskeard.  There is no vehicle parking within the site, and Pike Street has restricted staying times for vehicle parking within it.
A12.220A	USE OF THE SITE: Do not use the site for any purpose other than carrying out the works. The building will not remain in use and open to visitors for the entire period of the works. Wherever possible restrict the movement of large items of plant, materials and components around adjacent shop premises opening and closing times. Ensure public pavement thoroughway is maintained. The use of radios is not permitted. For temporary contractor's accommodation, workshop and storage facilities see clause A36.270.

**It should be noted that the Guildhall is in constant used by the client as well as the general public. All activities will continue to operate during the works.**

- A12.230      **SURROUNDING BUILDING USES:**  
The Guildhall is situated in a commercial area. At all times consideration must be given to making the delivery and movement of materials and plant and work operations as unobtrusive as possible.
- A12.240A      **RISKS TO HEALTH AND SAFETY:**  
The nature and condition of the site/building cannot be fully and certainly ascertained before it is opened up. However, the following risks are or may be present
- Former lead-based paints.
  - Working from height
- The contractor should liaise with the client at the start of the contract to ascertain any event are planned during the work period. Ensure work area is left clean and tidy and taking special care of any trip hazards.  
The accuracy and sufficiency of this information is not guaranteed by the Employer or the CA and the Contractor must ascertain for himself any information he may require to ensure the safety of all persons and the Works.
- A12.280      **SITE VISIT:** Before tendering, ascertain the nature of the site, access there to and all local conditions and restrictions likely to affect the execution of the Works.
- A12.290      **SITE VISIT** may be made by prior appointment with Simon Crosbie (Le Page Architects) 01752 849 880.
- A13              **DESCRIPTION OF THE WORK**
- A13.110      **THE WORK** Refurbishment of existing cast iron rainwater goods.
- A20              **THE CONTRACT**
- A20.910      **AGREEMENT FOR INTERMEDIATE JCT CONTRACT:** The form of contract will be a written agreement with at least the following general clauses
- The Works are to commence TBC 2025 and shall be completed  
By TBC 2025
- Liquidated damages: £250 per week.
- Defects liability period: 3 months.
- Retention percentage: 5%.
- Penultimate certificate percentage: 2.5%.
- Final Certificate:  
Period for supply of documentation: three months
- Injury or damage to property  
Insurance cover to be not less than £5,000,000
- Payment valuations fortnightly.
- 5.4 A-C Insurance clause Contractor All Risk (existing fabric and proposed works)
- Contractor to provide full RAMS for the works.

A30	TENDERING
A30.110	SCOPE: These conditions are supplementary to those stated in the invitation to tender and on the Form of Tender.
A30.120	TENDERING PROCEDURE will be in accordance with the principles of the 'Code of Procedure for Single Stage Selective Tendering' 1996.
A30.161	EXCLUSIONS: If the Contractor cannot tender for any part(s) of the work as defined in the tender documents he must inform the CA as soon as possible, defining the relevant part(s) and stating the reasons for his inability to tender.
A30.170	ACCEPTANCE OF TENDER: The Employer and his representative: <ul style="list-style-type: none"> <li>- Offer no guarantee that the lowest or any tender will be recommended for acceptance or accepted.</li> <li>- Will not be responsible for any cost incurred in the preparation of any tender.</li> </ul>
A30.191	PERIOD OF VALIDITY: Tenders must remain open for consideration (unless previously withdrawn) for not less than 13 weeks from the date fixed for the submission or lodgement of tenders. Information on the date for possession/commencement is given in section A20.
A30.315	PROJECTS WITHOUT QUANTITIES: Tenders must include for all work shown or described in the tender documents as a whole or clearly apparent as being necessary for the complete and proper execution of the Works.
A30.341	ERRORS IN THE PRICED DOCUMENTS will be dealt with in accordance with the 'Code of Procedure for Single Stage Selective Tendering' 1996, Alternative 1 (the word 'documents' being substituted for 'bills of quantities').
A30.535	SUBSTITUTE PRODUCTS: If the Contractor wishes to substitute products of different manufacture to those specified, details must be submitted with the tender giving reasons for each proposed substitution. Substitutions which have not been notified at tender stage may not be considered. Substitutions sanctioned by the CA will be subject to the verification requirements of clause A31.200.
A30.551	<p>HEALTH AND SAFETY INFORMATION: In line with CDM Regulations 2015, a construction phase plan is to be prepared by the principal contractor and submitted to the client and principal designer prior to the commencement of works. A Health and Safety File is to be provided and kept on site by the Principal Contractor. The Principal Contractor must ensure that they provide appropriate supervision, instruction and information; and that all workers have the right skills, knowledge, training and experience for the works being carried out.</p> <p>A statement must be submitted with the tender describing the organisation and resources which the contractor proposes and undertakes to provide to safeguard the health and safety of operatives, including those of subcontractors and of any person who may be affected by the works, including:</p> <p>A copy of the contractor's health and safety policy document, including risk assessment procedures.  Accident and illness records for the past five years.  Records of previous Health and Safety Executive enforcement action.  Records of training and training policy.  The number and type of staff responsible for health and safety on this project with details of their qualifications and duties.</p>

A31	PROVISION, CONTENT AND USE OF DOCUMENTS
	DEFINITIONS AND INTERPRETATIONS
A31.130	IN WRITING: When required to notify, inform, instruct, agree, confirm, obtain information, obtain approval or obtain instructions do so in writing.
A31.140	APPROVAL (and words derived there from) means the approval in writing of the CA unless specified otherwise.
A31.180	<p>CROSS-REFERENCES TO THE SCHEDULE OF WORKS:</p> <ul style="list-style-type: none"><li>- Where a numerical cross-reference to a Schedule of works section or clause is given on drawings or in any other document the Contractor must verify its accuracy by checking the remainder of the annotation or item description against the terminology used in the referred to section or clause.</li><li>- Where a numerical cross-reference is not given, the relevant section(s) and clause(s) of the schedule of works will apply, cross-reference thereto being by means of related terminology.</li><li>- Where a cross-reference for a particular type of work, feature, material or product is given, relevant clause(s) elsewhere in the referred to schedule of works section dealing with general matters, ancillary products and workmanship also apply.</li><li>- The Contractor must, before proceeding, obtain clarification or instructions in relation to any discrepancy or ambiguity which he may discover.</li></ul>
A31.200	<p>EQUIVALENT PRODUCTS:</p> <ul style="list-style-type: none"><li>- Where the schedule of works permits substitution of a product of different manufacture to that specified and such substitution is desired, before ordering the product notify the CA and, when requested, submit for verification documentary evidence that the alternative product is equivalent in respect of material, safety, reliability, function, compatibility with adjacent construction, availability of compatible accessories and, where relevant, appearance. Submit certified English translations of any foreign language documents.</li><li>- Any proposal for use of an alternative product must also include proposals for substitution of compatible accessory products and variation of details as necessary, with evidence of equivalent durability, function and appearance of the construction as a whole. If such substitution is sanctioned, and before ordering products, provide revised drawings, specification and manufacturer's guarantees as required by CA.</li></ul>
A31.201	EQUIVALENT PRODUCTS: Wherever products are specified by proprietary name and the phrase 'or equivalent' is not included, it is to be deemed included.
A31.225	REFERENCES TO BSI DOCUMENTS are to the versions and amendments listed in the BSI Standards Catalogue current at the date of tender.
A31.270	<p>SIZES: Unless otherwise stated:</p> <ul style="list-style-type: none"><li>- Products are specified by their co-ordinating sizes.</li><li>- Cross section dimensions of timber shown on drawings are nominal sizes before any required planning.</li></ul>
A31.280	FIX ONLY means all labours in unloading, handling, storing and fixing in position, including use of all plant.
A31.290	SUPPLY AND FIX: Unless stated otherwise all items given in the schedule of work and/or on the drawings are to be supplied and fixed complete.
	TERMS USED IN REFURBISHMENT/ALTERATION
A31.311	REMOVE means:

- disconnect, dismantle as necessary and remove the stated element, work or component and all associated accessories, fastenings, supports, linings and bedding materials, and dispose of unwanted materials.

It does not include:

- Removing associated pipework, wiring, ductwork or other services.

A31.321 KEEP FOR REUSE means:

- During removal prevent damage to the stated components or materials, and clean off bedding and jointing materials.
- Stack neatly, adequately protect and store until required by the Employer or for use in the Works as instructed.

A31.331 REPLACE means:

- Remove the stated existing components, features and finishes.
- Provide and fit in lieu new components, features or finishes that, unless specified otherwise, must match those that have been removed.
- Make good as necessary.

A31.341 REPAIR means:

- Carry out local remedial work to components, features and finishes as found in the existing building, resecure or refix as necessary and leave in a sound and neat condition. It does not include:
- Replacement of components or parts of components.
- Redecoration.

A31.351 MAKE GOOD means:

- Carry out local remedial work to components, features and finishes which have been disturbed by other, previous work under this Contract and leave in a sound and neat condition.

It does not include:

- Replacement of components or parts of components.
- Redecoration. The meaning of the term shall not be limited by this definition where used in connection with the defects liability provisions of the Contract.

A31.361 EASE means:

- Make minor adjustments to moving parts of the stated component to achieve good fit in both open and closed positions and ensure free movement in relation to fixed surrounds. Make good as necessary.

A31.371 TO MATCH EXISTING means:

- Use products, materials and methods to match closely all visual characteristics and features of the existing work, with joints between existing and new work as inconspicuous as possible, all to approval of appearance.

#### ***DOCUMENTS PROVIDED ON BEHALF OF EMPLOYER***

A31.410 ADDITIONAL COPIES OF DRAWINGS: Two copies of documents (not counting any certified copy of the Contract Documents) will be issued to the Contractor free of charge. Additional copies will be issued on request but will be charged to the Contractor.

A31.430 ADDITIONAL COPIES OF SPECIFICATION: After execution of the Contract, two copies of the Specification will be issued to the Contractor in accordance with the Contract. Additional copies will be issued on request, if available, but will be charged to the Contractor.

A31.440 DIMENSIONS: The accuracy of dimensions scaled from the drawings is not guaranteed. Obtain from the CA any dimensions required but not given in figures on the drawings nor calculable from figures on the drawings.

- A31.460 THE SPECIFICATION: All sections of the specification must be read in conjunction with Main Contract Preliminaries/General conditions.
- A31.480 TECHNICAL DOCUMENTS: Copies of Lead Sheet Association Manuals are available for inspection by appointment during normal office hours at the office of the CA.
- DOCUMENTS PROVIDED BY CONTRACTOR
- A31.711 TECHNICAL LITERATURE: The Contractor is required to keep copies of the following on site, readily accessible for reference by all supervisory personnel:
- Manufacturers' current technical literature relating to all products to be used in the Works.
  - Those parts of BS 8000 'Workmanship on Building Sites', which are invoked in the schedule of works.
- A31.720 MAINTENANCE INSTRUCTIONS AND GUARANTEES:  
Retain copies delivered with components and equipment (failing which, obtain), register with manufacturer as necessary and hand over to CA on or before Practical Completion.
- A31.721 AS BUILT DRAWINGS  
Provide 1 coloured set of 'As Built' drawings indicating all final completed works
- A32 MANAGEMENT OF THE WORKS
- A32.120 INSURANCES: Before starting work on site submit documentary evidence and/or policies and receipts for the insurances required by the Conditions of Contract.
- A32.130 INSURANCE CLAIMS: If any event occurs which may give rise to any claim or proceeding in respect of loss or damage to the Works or injury or damage to persons or property arising out of the Works, forthwith give notice in writing to the Employer, the CA and the Insurers. Indemnify the Employer against any loss, which may be caused by failure to give such notice.
- A32.150 OWNERSHIP: Materials arising from the alteration work are to become the property of the Contractor except where otherwise stated. Remove from site as work proceeds.
- A32.212 PROGRAMME:
- As soon as possible and before starting work on site prepare in an approved form a programme for the Works, which must make allowance for all:
  - Planning and mobilisation by the Contractor
  - Subcontractor's work
  - Work resulting from instructions issued in regard to the expenditure of provisional sums
  - Submit two copies to the CA.
- A32.261 CA'S SITE MEETINGS:
- The CA will hold site meetings to review progress and other matters. Meetings will normally be held as required.
  - Ensure the availability of accommodation and attend all such meetings.
  - The CA will chair the meetings and take and distribute minutes.
- A32.290 NOTICE OF COMPLETION: Give CA at least two weeks notice of the anticipated dates of Practical Completion of the whole or parts of the Works.
- A32.410 CASH FLOW FORECAST: Submit with the tender a forecast showing the gross valuation of the Works at the date of each Interim Certificate throughout the Contract period and based upon the programme for the Works.

- A32.420      EXISTING WORK: The extent and location of renewal of existing work must be agreed, at least on a provisional basis, with the CA before the work is started. Remove existing work in ways, which will reasonably minimise the amount of removal and renewal.
- A32.430      ESTIMATED COST OF VARIATIONS: If the CA issues details of a proposed instruction with a request for an estimate of cost, submit such an estimate without delay and in any case within 7 days.
- A32.461      INTERIM VALUATIONS: At least 7 days before the established dates for interim valuations submit to the Architect details of amounts due under the Contract together with all necessary supporting information.
- A33           QUALITY STANDARDS/CONTROL
- MATERIALS AND WORK GENERALLY
- A33.110      GOOD PRACTICE: Where and to the extent that materials, products and workmanship are not fully detailed or specified they are to be:
- Of a standard appropriate to the Works and suitable for the functions stated in or reasonably to be inferred from the project documents, and
  - In accordance with relevant good building practice.
- A33.121      GENERAL QUALITY OF PRODUCTS:
- Products to be new unless otherwise specified.
  - For products specified to a British or European Standard obtain certificates of compliance from manufacturers when requested.
  - Where a choice of manufacturer or source is allowed for any particular product, the whole quantity required must be of the same type, manufacture and/or source unless otherwise approved. Produce written evidence of sources of supply when requested.
  - Ensure that the whole quantity of each product required is of consistent kind, size, quality and overall appearance.
  - Where consistency of appearance is desirable ensure consistency of supply from the same source. Do not use different colour batches where they can be seen together.
  - If products are prone to deterioration or have a limited shelf life, order in suitable quantities to a programme and use in appropriate sequence. Do not use if there are any signs of deterioration, setting or other unsatisfactory condition.
- A33.131      PROPRIETARY PRODUCTS:
- Handle, store, prepare and use or fix each product in accordance with its manufacturer's current printed or written recommendations. Inform CA if these conflict with any other specified requirement. Submit copies when requested.
  - The tender will be deemed to be based on the products specified and recommendations on their use given in the manufacturers' literature current at the date of tender.
  - Where British Board of Agrément certified products are used, comply with the limitations, recommendations and requirements of the relevant valid certificates.
- A33.141      CHECKING COMPLIANCE OF PRODUCTS: Check all documentation and the products themselves to ensure compliance with the project documents. Where different types of any product are specified, check to ensure that the correct type is being used in each location. In particular, check that:
- The sources, types, qualities, finishes and colours are correct, and match any approved samples.
  - All accessories and fixings which should be supplied with the products have been supplied.
  - Sizes are correct. Where tolerances are critical, measure a sufficient quantity to ensure compliance.



- The delivered quantities are correct, to ensure that shortages do not cause delays in the work.
- The products are clean, undamaged and in good condition.
- Products which have a limited shelf life are not out of date.

A33.151

**PROTECTION OF PRODUCTS**

- Prevent over-stressing, distortion and other damage.
- Keep clean and free from contamination. Prevent staining, chipping, scratching or other disfigurement, particularly of products exposed to view in the finished work. Keep dry to prevent premature setting, moisture movement and similar defects. Where appropriate store off the ground and allow free air movement between stored products.
- Prevent excessively high or low temperatures and rapid changes of temperature in the products.
- Protect adequately from rain, damp frost, sun and other elements as appropriate. Ensure that products are at a suitable temperature and moisture content at time of use.
- Ensure that sheds and covers are of ample size, in good weatherproof condition and well secured.
- Keep different types and grades of products separately and adequately identified.
- Keep products in their original wrappings, packings or containers until immediately before they are used. Wherever possible retain protective wrappings after fixing and until shortly before Practical Completion.
- Ensure that protective measures are fully compatible with and not prejudicial to the products/materials.

A33.161

**SUITABILITY OF RELATED WORK AND CONDITIONS:** Provide all trades with necessary details of related types of work. Before starting each type of work, ensure that:

- Previous work is appropriately complete, in accordance with the project documents, to a suitable standard and in a suitable condition to receive the new work.
- All necessary preparatory work has been carried out, including provision for services, openings, supports, fixings, damp proofing, priming and sealing.
- The environmental conditions are suitable, particularly that the building is suitably weather tight.

A33.171

**GENERAL QUALITY OF WORKMANSHIP:**

- Operatives must be appropriately skilled and experienced for the type and quality of work.
- Take all necessary precautions to prevent damage to the work from frost, rain and other hazards.
- Inspect components and products carefully before fixing or using and reject any which are defective.
- Fix or lay securely, accurately and in alignment.
- Provide suitable packings at screwed and bolted fixings to take up tolerances and prevent distortion. Do not over tighten.
- Adjust location and fixing of components and products so that joints which are open to view are even and regular.
- Ensure that all moving parts operate properly and freely. Do not cut, grind or plane pre-finished components and products to remedy binding or poor fit without approval.

A33.181

**BS 8000: BASIC WORKMANSHIP**

- Where BS 8000 gives recommendations on working methods, compliance will be deemed to be a matter of industry good practice and not a requirement of the CA.
- If there is any conflict or discrepancy between the recommendations of BS 8000 on the one hand and the project documents on the other, the latter will prevail.

A33.191 WATER FOR THE WORKS: If other than mains supply is proposed provide evidence of suitability.

#### SAMPLES/APPROVALS

A33.211 SAMPLES: Where approval of a product is specified the requirement for approval relates to a sample of the product and not to the product as used in the Works. Submit a sample or other evidence of suitability. Do not confirm orders or use the product until approval of the sample has been obtained. Retain approved sample in good, clean condition on site. Ensure that the product used in the Works matches the approved sample.

A33.230 APPROVALS: Where and to the extent that products or work are specified to be approved or the CA instructs or requires that they are to be approved, the same must be supplied and executed to comply with all other requirements and in respect of the stated or implied characteristics either:

- To the express approval of the CA or
- To match a sample expressly approved by the CA as a standard for the purpose.

#### ACCURACY/SETTING OUT GENERALLY

A33.321 SETTING OUT: Check the levels and dimensions of the site against those shown on the drawings, and record the results on a copy of the drawings. Notify CA in writing of any discrepancies and obtain instructions before proceeding.

A33.322 SETTING OUT: Inform CA when overall setting out is complete and before commencing construction.

A33.341 APPEARANCE AND FIT:

- Arrange the setting out, erection, juxtaposition of components and application of finishes to ensure satisfactory fit at junctions, no practically or visually unacceptable changes in plane, line or level and a true, regular finished appearance.
- Wherever satisfactory accuracy, fit and/or appearance of the work are likely to be critical or difficult to achieve obtain approval of proposals or of the appearance of the relevant aspects of the partially finished work as early as possible.

#### SERVICES GENERALLY

A33.410 SERVICES REGULATIONS: Any work carried out to or which affects new or existing services must be in accordance with the Bye Laws or Regulations of the relevant Statutory Authority.

A33.420 SERVICE RUNS: Make adequate provision for services, including unobstructed routes and fixings. Wherever possible ducts, chases and holes are to be formed during construction rather than cut.

A33.440 MECHANICAL AND ELECTRICAL SERVICES must have final tests and commissioning carried out so that they are in full working order at Practical Completion.

#### SUPERVISION/INSPECTION/DEFECTIVE WORK

A33.550 DEFECTS IN EXISTING CONSTRUCTION to be reported to CA without delay. Obtain instructions before proceeding with work which may:

- Cover up or otherwise hinder access to the defective construction, or
- Be rendered abortive by the carrying out of remedial work.

A33.560 TIMING OF TESTS AND INSPECTIONS: Agree dates and times of tests and inspections with CA several days in advance, to enable the CA and other affected parties to be present. On the previous working day to each such test or inspection

confirm that the work or sample in question will be ready or, if not ready, agree a new date and time.

- A33.570 PROPOSALS FOR RECTIFICATION OF DEFECTIVE WORK/PRODUCTS:
- As soon as possible after any part(s) of the work or any products are known to be not in accordance with the Contract, or appear that they may not be in accordance, submit proposals to CA for opening up, inspection, testing, making good, adjustment of the Contract Sum, or removal and re-execution.
  - Such proposals may be unacceptable to the CA, and he may issue contrary instructions.

#### WORK AT OR AFTER COMPLETION

- A33.611 GENERALLY:
- Make good all damage consequent upon the work.
  - Remove all temporary markings and protective coverings.
  - Clean the works thoroughly inside and out including all accessible ducts and voids, remove all splashes, deposits, efflorescence, rubbish and surplus materials.
  - Cleaning materials and methods to be as recommended by manufacturers of products being cleaned, and to be such that there is no damage or disfigurement to other materials.
  - Obtain COSHH dated data sheets for all materials used for cleaning and ensure they are used only as recommended by their manufacturers.
  - Touch up minor faults in newly painted/repainted work, carefully matching colour. Repaint badly marked areas back to suitable breaks or junctions.
  - Adjust, ease and lubricate moving parts as necessary to ensure easy and efficient operation, including doors, windows, drawers, ironmongery, appliances, valves and controls.

- A33.640 SECURITY AT COMPLETION: Leave the Works secure with all accesses locked. Account for and adequately label all keys and hand over to Employer with itemised schedule, retaining duplicate schedule signed by Employer as a receipt.

- A33.650 MAKING GOOD DEFECTS: Make arrangements with the Employer and give reasonable notice of the precise dates for access to the various parts of the Works for purposes of making good defects. Inform CA when remedial works to the various parts of the Works are completed.

#### A34 SECURITY/SAFETY/PROTECTION

##### GENERALLY

- A34.110 THE PRE-CONSTRUCTION INFORMATION PACK prepared by the Planning Supervisor, is a separate document but forms part of the Tender and Contract documents.
- A34.114 CONSTRUCTION HAZARDS particular to this contract are identified in the Pre-Construction Information Pack (Risk Assessment Sheets). Commonplace hazards, which should be controlled by good management and good site practices, as part of compliance with the Health & Safety at Work Act, are not listed.
- A34.117 HEALTH HAZARDS arising from the specified construction materials are identified in the Pre-Tender Health & Safety Plan (Risk Assessments). Commonplace hazards which should be controlled by good management and good site practices as part of compliance with the Health & Safety at Work Act, are not listed.
- A34.121 THE CONSTRUCTION PHASE HEALTH AND SAFETY PLAN. The Health & Safety Plan (Construction Stage) is to be developed from the Pre-tender Health and Safety Plan must be submitted to the CA not less than two weeks before the proposed date for start on site. Work must not commence until the Employer, as advised by the

Planning Supervisor, has confirmed in writing that in his view the Health & Safety Plan (Construction Stage) satisfies the requirements of the Construction Design and Management Regulations.

- A34.125 HSE APPROVED CODES OF PRACTICE: Comply with the following:
- Management of health and safety at work.
  - Managing construction for health and safety.
- A34.130 SECURITY:  
Adequately safeguard the site, the Works, products, materials, plant, and any existing buildings affected by the Works from damage and theft. Take all reasonable precautions to prevent unauthorised access to the site, the Works and adjoining property.
- A34.140 STABILITY: Accept responsibility for the stability and structural integrity of the Works during the Contract, and support as necessary. Prevent overloading: details of design loads may be obtained from CA.
- A34.150A OCCUPIED PREMISES:
- The Guildhall will remain open to visitors for the entire period of the works
  - Wherever possible restrict the movement of large items of plant, materials and components around the arrival of groups and services.
  - There is an intruder alarm and contractors are to be mindful of security of adjacent premises/traders
  - Ensure public thoroughway is maintained along West Street and Barras Place at all times.
  - Carry out the Works without undue inconvenience and nuisance and without danger to occupants and users.
  - If it transpires that compliance with this clause requires certain operations to be carried out during overtime, and such overtime is not required for any other reason, the extra cost will be paid to the Contractor, provided that such overtime is authorised by the CA in advance.
- A34.170 EMPLOYER'S REPRESENTATIVES SITE VISITS:  
Inform the CA in advance of all safety provisions and procedures (including those relating to materials which may be deleterious) that will require the compliance of the Employer or his representatives when visiting the site. Provide protective clothing and/or equipment for the Employer and his representatives as appropriate.

**PROTECT AGAINST THE FOLLOWING:**

- A34.221 NOISE:
- Comply generally with the recommendations of BS 5228: Part 1, clause 9.3 for minimising noise levels during the execution of the works.
  - Fit all compressors, percussion tools and vehicles with effective silencers of a type recommended by manufacturers of the compressors, tools or vehicles.
  - Do not use pneumatic drills and other noisy appliances during 9am to 5pm without consent of the CA.
  - The use of radios or other audio equipment is not permitted.
- A34.231 POLLUTION: Take all reasonable precautions to prevent pollution of the site, the Works and the general environment including streams and waterways.
- A34.235 USE OF PESTICIDES:
- Use only where specified or approved, and then only suitable products as listed in the UK Pesticide Guide.
  - Where work is near water, drainage ditches or land drains, comply with the MAFF guidelines for the use of herbicides on weeds in or near water courses and lakes.
  - Observe all precautions recommended by the manufacturer and remove containers from site immediately they have been emptied or are no longer required.

- Operatives must hold a BASIS Certificate of Competence, or work under the supervision of a Certificate holder.
- A34.240 NUISANCE: Take all necessary precautions to prevent nuisance from smoke, dust, rubbish, vermin and other causes.
- A34.241 PROTECTED SPECIES  
Take all necessary precautions to prevent harm to bats, birds etc. Generally, check all voids, materials etc where scheduled works are to take place for life before commencing. If any protected species are discovered work is to cease IMMEDIATELY and the CA informed.
- A34.250 ASBESTOS BASED MATERIALS: Report immediately to the CA any suspected asbestos based materials discovered during demolition/refurbishment work. Avoid disturbing such materials. Agree with the CA methods for safe removal or encapsulation.
- A34.260 FIRE PREVENTION: Take all necessary precautions to prevent personal injury, death, and damage to the Works or other property from fire. Comply with Joint Code of Practice 'Fire Prevention on Construction Sites' published by the Building Employers Confederation and the Loss Prevention Council.
- A34.263 FIRE PREVENTION: Smoking will not be permitted on the site except in designated areas which must be carefully controlled equipped with fire fighting equipment and receptacles for the safe disposal of smokers materials and inspected to guard against risk of fire.
- A34.265 BURNING ON SITE of materials arising from the work will not be permitted.
- A34.280 MOISTURE: Prevent the work from becoming wet or damp where this may cause damage. Dry out the Works thoroughly. Control the drying out and humidity of the Works and the application of heat to prevent:
  - Blistering and failure of adhesion.
  - Damage due to trapped moisture.
  - Excessive movement.
- A34.285 INFECTED TIMBER: Where instructed to remove timber affected by fungal/insect attack from the building, do so in a way which will minimise the risk of infecting other parts of the building.
- A34.290 WASTE:
  - Remove rubbish, debris, surplus material and spoil regularly and keep the site and Works clean and tidy.
  - Remove all rubbish, dirt and residues from voids and cavities in the construction before closing in.
  - All ground areas to be kept free of broken slates and roofing nails to prevent Health & Safety risks and damage to gardening equipment.
  - Ensure that non-hazardous material is disposed of at a tip approved by a Waste Regulation Authority.
  - Remove all surplus hazardous materials and their containers regularly for disposal off site in a safe and competent manner as approved by a Waste Regulation Authority and in accordance with relevant regulations.
  - Retain waste transfer documentation on site.

**PROTECT THE FOLLOWING:**

- A34.410 WORK IN ALL SECTIONS: Adequately protect all types of work and all parts of the Works, including work carried out by others, throughout the Contract. Wherever work is of an especially vulnerable nature or is exposed to abnormal risks provide special protection to ensure that damage does not occur.

- A34.421      **EXISTING SERVICES:**
- Notify all service authorities and adjacent owners of the proposed works not less than one week before commencing site operations.
  - Before starting work check positions of existing services.
  - Observe service authorities' recommendations for work adjacent to existing services. Do not interfere with their operation without consent of the service authorities or other owners.
  - If any damage to services results from the Works, notify CA and appropriate service authority without delay. Make arrangements for making good without delay to the satisfaction of the service authority or other owner as appropriate.
  - Replace marker tapes or protective covers disturbed by site operations to the service authority's recommendations.
  - ENSURE THE EXISTING BUILDING HAS THE CAPACITY FOR AND FURTHER LOADING TO IT FROM PROPOSED WORKS. INFORM THE CA AT TIME OF TENDER IF SUCH IS SUSPECTED.
- A34.430      **ROADS AND FOOTPATHS:** Adequately maintain roads and footpaths within and adjacent to the site and keep clear of mud and debris. Any damage to roads and footpaths caused by site traffic or otherwise consequent upon the Works must be made good to the satisfaction of the Local Authority or other owner. Bear any costs arising.
- A34.440      **RETAINED TREES/HEDGES/SHRUBS/GRASSED AREAS:**
- Adequately protect and preserve, except those that are to be removed.
  - Replace to approval or treat as instructed any species or areas damaged or removed without approval.
  - Mature trees and shrubs which, due to the Contractor's negligence, are uprooted, destroyed, or in the opinion of the CA, damaged beyond reasonable chance of survival in their original shape, must be replaced with those of a similar type and age at the Contractor's expense.
- A34.450      **EXISTING FEATURES:** Prevent damage to existing buildings, headstones, graves, fences, gates, walls, roads, paved areas and other site features which are to remain in position during the execution of the Works.
- A34.460      **EXISTING WORK:** Prevent damage to existing property undergoing alteration or extension and make good to match existing any defects so caused. Remove existing work the minimum necessary and with care to reduce the amount of making good to a minimum.
- A34.461A      **SPECIAL PROTECTION:**
- A34.465      **BUILDING INTERIORS:** Protect building interiors exposed to the weather during the course of alteration work with temporary enclosures of sufficient size to permit execution of the work and which will remain weathertight in severe weather.
- A34.470      **EXISTING FURNITURE, FITTINGS AND EQUIPMENT:** Prevent damage to any furniture, fittings or equipment left in the existing property. Move as necessary to enable the Works to be executed, cover and protect as necessary and replace in original positions.
- A34.481      **ADJOINING PROPERTY:** Prevent trespass of workpeople. Take all reasonable precautions to prevent damage to adjoining property. Obtain permission as necessary from the owners if requiring to erect scaffolding on or otherwise use adjoining property, and pay all charges. Clear away and make good on completion or when directed. Bear the cost of repairing any damage arising from execution of the Work.
- A34.490      **EXISTING STRUCTURES:**
- Provide and maintain during the execution of the Works all incidental shoring, strutting, needling and other supports as may be necessary to preserve the

	<p>stability of existing structures on the site or adjoining, that may be endangered or affected by the Works.</p> <ul style="list-style-type: none"> <li>- Support existing structure as necessary during cutting of new openings or replacement of structural parts.</li> <li>- Do not remove supports until new work is strong enough to support the existing structure. Prevent overstressing of completed work when removing supports.</li> </ul>
A35	SPECIFIC LIMITATIONS ON METHOD/SEQUENCE/TIMING
A35.140	ACCESS TO THE SITE: See section A12.
A35.150	USE OF THE SITE: See section A12.
A35.190	WORKING HOURS: 7.30am to 5.30pm Monday to Friday weekend working only by prior arrangement with the client.
A36	FACILITIES/TEMPORARY WORK/SERVICES
A36.110	LOCATIONS: Inform CA of the intended siting of all spoil heaps, temporary works and services.
A36.120	MAINTAIN, alter, adapt and move temporary works and services as necessary. Remove when no longer required and make good.
A36.270	<p>ACCOMMODATION INCLUDED IN THE SITE: Use of the following areas for the duration of the Contract without change, may be assumed by the Contractor:</p> <p>Public Hall First Floor Toilets, Kitchenette and site welfare space ( TBC)</p> <p>As long as:</p> <ul style="list-style-type: none"> <li>- It is used solely for the purposes of carrying out the Works.</li> <li>- The use to which it is put must not involve undue risk of damage.</li> <li>- Any temporary adaptations must be approved by or on behalf of the Employer before being carried out.</li> <li>- It must be vacated on completion of the Works or determination of the Contract.</li> <li>- When vacated, its condition must be at least equivalent to its condition at the start of the Contract including making good of ground/floor surfaces.</li> <li>- The spaces used are cleaned down at the end of each working week.</li> </ul> <p>Available services:</p> <ul style="list-style-type: none"> <li>- Services within the building include water and electrics. These will be free of charge to the contractor for use of the works only.</li> </ul>
A36.281	EXISTING ACCOMMODATION: The Guildhall may not be used for sitting of any other temporary accommodation/plant not associated with the works.
A36.410	LIGHTING: During finishing work and inspection provide temporary lighting, the intensity and direction of which closely resembles that provided by the permanent installation.
A36.420	<p>LIGHTING AND POWER: Electricity supply from the Employer's mains may be used for the Works. It is the contractor's responsibility to establish the point of supply, anticipated capacity and supply voltage.</p> <p>The Employer will not be held responsible for the effects of any failure or restriction in supply.</p>
A36.431	WATER: Contractor is responsible for connecting a temporary water supply from the as agreed on site with the CA. The temporary system shall be made good upon completion of the project.

- A36.442      TELEPHONES: Provide as soon as practicable after the Date of Possession a joint temporary on site office telephone for use by the Contractor, Subcontractors and those acting on behalf of the Employer. Make arrangements (e.g. an external bell) to ensure that incoming calls are answered reasonably promptly. Allow for the cost of a modest number of calls made by those acting on behalf of the Employer.
- A36.445      TELEPHONES: Provide as soon as practicable a means of direct telephone communication with the Contractor's person-in-charge.
- A36.500      METER READINGS: Project specific - to be adapted as required. Where charges for service supplies need to be apportioned ensure that meter readings are taken by relevant authority at possession and/or completion as appropriate. Ensure that copies of readings are supplied to interested parties.
- A36.511      THERMOMETER: Provide on site and maintain in accurate condition a maximum and minimum thermometer for measuring atmospheric shade temperature, in an approved location.