



Church and Public Clock Specialists. Castle Workshops, Dacre, Penrith, Cumbria.  
CA11 0HL.

Telephone: 017684 86933

Email: [info@clockmaker.co.uk](mailto:info@clockmaker.co.uk).

Website: [www.clockmaker.co.uk](http://www.clockmaker.co.uk)

11<sup>th</sup> October 2021, Revised 9<sup>th</sup> April 2026

**FAO - Jacqui Orange**

Facilities Manager

Liskeard Town Council

Dear Jacqui

**Liskeard Town Hall – Tower Clock**

Further to your telephone conversation with our office, we are pleased to provide a revised quotation to automatically wind the clock movement & fit an auto regulator.

The proposed automatic winding units would be situated below the clock movement with the drive being via the barrel arbors, which meets the current conservation code of practice. The weights would fall down the existing weight chute or operate within the clock room.

These winding units can be supplied as mains driven or battery driven depending on the frequency and duration of power failures. Battery backed units should always be installed when there is a possibility of power failures lasting more than 24 hours.

Where power failures are only a few hours' long mains driven units are preferred.

The cost is shown in quotation 1.

**The automatic winding units manufactured by the Cumbria Clock Company are the only units to come complete with a ten-year guarantee.**

After the winding units have been fitted it must be realized that the clocks time keeping is still regulated by the pendulum. Therefore, it will still be necessary for somebody to attend to the regulation & undertake the summer & wintertime changes.

We can if necessary, fit an auto-regulation system to undertake these procedures if it proves difficult to find somebody to do so. We have submitted quotation 2 for one of

these systems, which will provide accurate time keeping, & automatic BST/GMT alterations.

The following quotations do not include the cost of installing a suitable power supply for the winding units or the regulator to be connected to.

### **Quotation 1 - Automatic winding**

Attend on site take details & confirm electrical requirements.

Manufacture 3x 240volt mains epicyclic automatic winding units.

To manufacture three split sprockets to fit barrel arbors of the quarter, striking and going trains.

Attend onsite and land weights and disconnect existing weight lines.

Fit sprockets to barrel arbors.

Install automatic winding units and hang weights.

Test and leave in full working order.

**For the sum of ... £8,910 [Eight Thousand, Nine Hundred & Ten Pounds] net plus VAT.**

### **Quotation 2 – Auto Regulator**

Manufacture, an auto regulator system to provide accurate time keeping & automatic BST/GMT alterations.

Attend on site & install

**For the sum of ... £2,805 [Two Thousand, Eight Hundred & Five Pounds] net plus VAT**

### **Exclusions**

The provision of a suitable electrical supply in the form of 3x 13amp sockets for quotation 1, please note they are fused at 5amps & an additional socket for quotation 2. The details & positions of the power points would be confirmed on our first visit to site.

### **Price Maintenance**

These prices are firm for a period of six months from the date of this letter and thereafter, subject to price increase to accord with increased costs of labour, materials and travelling costs if necessary.

## **Guarantees**

All new parts made by us carry our ten-year guarantee against failure through faulty workmanship or materials. Repair work is similarly guaranteed for a period of twelve months. Suspension springs and electrical or electronic components of units not of our manufacture, are specifically excluded from our guarantees, but carry the manufacturers own warranty.

## **Terms Payment**

30% with orders over £ 1,000.00, the balance within 14 days of the date of invoice following completion of the work.

In some cases progress payments may be asked for.

All goods remain the property of the vendor until full payment has been made and any relevant cheques cleared. Risk passes on delivery.

The above quotation is exclusive of Value Added Tax at 20%.

**The Cumbria Clock Company Ltd complies with the “Code of Practice for Turret Clock Work” produced by the Clocks Advisers Forum of DAC Clock Advisers in collaboration with Turret Clock Companies and the Church Buildings Council.**

Trusting the above information is helpful to you, but in the event you should have any questions to ask, please do not hesitate to contact us.

We assure you of our best care and attention, at all times and look forward to hearing from you in the near future.

Yours sincerely

Keith Cotton.

Technical Sales Manager

Church and Public Clock Specialists.  
Castle Workshops.  
Dacre, Penrith, Cumbria. CA11 0HL

Telephone: 017684 86933 Mobile.07802332774  
www.clockmaker.co.uk  
keithcotton@clockmaker.co.uk